

last modified: 09/13/21 printed: 09/13/21 by bk K:\Projects\2019\19038 Cape View Way\Drawings\19038 DE.dwg

GENERAL CONSTRUCTION NOTES:

- 1. ALL SITE WORK TO COMPLETE THIS PROJECT AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATIONS IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
2. IMMEDIATELY CONTACT AND COORDINATE WITH THE ENGINEER AND OWNER IF ANY DEVIATION OR ALTERATION OF THE WORK PROPOSED ON THESE DRAWINGS IS REQUIRED.
3. UTILIZE ALL PRECAUTIONS AND MEASURES TO ENSURE THE SAFETY OF THE PUBLIC, ALL PERSONNEL AND PROPERTY DURING CONSTRUCTION IN ACCORDANCE WITH OSHA STANDARDS...

BASIC CONSTRUCTION SEQUENCE:

- 1. THE FOLLOWING CONSTRUCTION SEQUENCE IS TO BE USED AS A GENERAL GUIDELINE. COORDINATE WITH THE OWNER, ENGINEERS, AND LANDSCAPE ARCHITECT AND SUBMIT A PROPOSED CONSTRUCTION SEQUENCE FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.
2. SURVEY AND STAKE THE PROPOSED LIMIT OF DISTURBANCE AND LIMIT OF SEDIMENTATION BARRIERS.
3. IDENTIFY AND MARK INVASIVE SPECIES. PLANT IDENTIFICATION SHALL BE PERFORMED BY QUALIFIED PERSONNEL ONLY, AS INDICATED IN THE SPECIFICATIONS.

EROSION & SEDIMENT CONTROL NOTES:

- 1. PRIOR TO THE START OF CONSTRUCTION A NOTICE OF INTENT (NOI) MUST BE FILED WITH NPDES. REFER TO THE STORMWATER AND POLLUTION PREVENTION PLAN (SWPPP) REGARDING ALL EROSION CONTROL MATTERS. MAINTAIN A WORKING COPY OF THE SWPPP ON-SITE AT ALL TIMES. FOLLOW THE SWPPP PROTOCOL FOR SITE MAINTENANCE, INSPECTIONS AND PROPER DOCUMENTATION UNTIL THE SITE HAS BEEN ACCEPTED BY THE OWNER.
2. DESIGNATE THE SITE CONSTRUCTION FOREMAN AS THE ON-SITE PERSONNEL RESPONSIBLE FOR THE DAILY INSPECTION AND MAINTENANCE OF ALL SEDIMENT AND EROSION CONTROLS AND IMPLEMENTATION OF ALL NECESSARY MEASURES TO CONTROL EROSION AND PREVENT SEDIMENT FROM LEAVING THE SITE.

STORMWATER FACILITY OPERATION & MAINTENANCE:

- THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER INSPECTION AND MAINTENANCE OF ALL STORMWATER MANAGEMENT FACILITIES AS OUTLINED BELOW DURING CONSTRUCTION AND UNTIL SUCH TIME THAT THE ROADWAYS AND ASSOCIATED UTILITIES ARE ACCEPTED BY THE OWNER AND THE ENGINEER.
1. INSPECT AND RESTORE/CLEAN ALL FACILITIES (INLETS, MANHOLES, INFILTRATION BASINS, STORMWATER MANAGEMENT AREAS AS DESCRIBED BELOW OF SEDIMENT AND DEBRIS PRIOR TO THE OWNER'S ACCEPTANCE.
2. REMOVE AND DISPOSE ALL SEDIMENT AND DEBRIS TO A PRE-APPROVED LOCATION.

WATER & SEWER INSTALLATION NOTES

- 1. INSTALL SEWER AND WATER MAINS ACCORDING TO THE FOLLOWING GUIDELINES TO PREVENT FREEZING OF THE MAIN OR SEWER:
UTILITY TYPE MIN. COVER OVER TOP OF PIPE MIN. HORIZONTAL DISTANCE TO DRAIN STRUCTURE
SANITARY FORCE MAIN 5 3
GRAVITY FORCE MAIN 4 2
WATER MAIN 5 2

WATER SYSTEM INSTALLATION NOTES:

- 1. CONSTRUCT THE WATER MAIN AND ITS APPURTENANCE IN ACCORDANCE WITH THE LOCAL WATER DEPARTMENTS STANDARDS AND SPECIFICATIONS AND PAY FOR ALL ASSOCIATED FEES AS REQUIRED BY THE WATER DEPARTMENT.
2. ALL PROPOSED WATER MAIN 4-INCHES AND GREATER IN DIAMETER ARE DUCTILE IRON CLASS 52. ONLY USE HDPE 3608 OR AS INDICATED ON DRAWINGS OR AS APPROVED BY THE ENGINEER.

SEWER SYSTEM OPERATION & MAINTENANCE:

- 1. CLEAN ALL NEWLY INSTALLED FACILITIES, INCLUDING SEWER COLLECTION SYSTEM OF ALL FOREIGN MATERIALS SUCH AS DIRT AND MISCELLANEOUS DEBRIS PRIOR TO SYSTEM TESTING. TESTING MUST BE WITNESSED AND INSPECTED BY THE ENGINEER. NO TESTING IS ALLOWED WITHOUT REMOVAL OF ALL FOREIGN MATERIALS.
2. CONDUCT A LEAKAGE TEST OF ALL SEWER MAINS. TEST MUST BE WITNESSED BY THE ENGINEER. THE CONTRACTOR MUST PROVIDE THE ENGINEER WITH A MINIMUM OF 48-HOURS ADVANCE NOTICE TO THE TIME OF THE PRESSURE TEST.

LEGEND:

Table with columns: GENERAL, SYMBOLS, BUILDING, and ENVIRONMENTAL. Lists various symbols and their corresponding descriptions like BENCHMARK, BOUNDARY, CONTROL POINT, etc.

Project information block containing: Revisions table, Project Name (CAPE VIEW WAY PERMITTING PLANS BOURNE, MASSACHUSETTS), Date (SEPTEMBER 2021), Drawn By (EWH), Checked By (BRK), and Registration stamp for Richard A. Clayton, Professional Engineer.

RECEIVED OCT 18 2021 Bourne Health Department 24 Perry Avenue Buzzards Bay, MA 02532

PERMITTING SET ONLY NOT FOR CONSTRUCTION

Project Number: 19038 Sheet: 2 of 23 Sheet Number: C - 2