

# CAPE VIEW WAY PERMITTING PLANS BOURNE, MASSACHUSETTS MARCH 5, 2021 SEPTEMBER 2021 **REVISED DECEMBER 2021** REVISED DECEMBER 21, 2022





VICINITY MAP **Graphic Scale** 1-inch = 1000-feet

PERMITTING SET ONLY NOT FOR CONSTRUCTION

## Sheet List Table

Sheet Number	Sheet Title
1	COVER
2	CONSTRUCTION NOTES
3	SITE PREP AND DEMO PLAN
4	OVERALL SITE PLAN
5	SITE LAYOUT PLAN (1)
6	SITE LAYOUT PLAN (2)
7	GRADING & DRAINAGE PLAN (1)
8	GRADING & DRAINAGE PLAN (2)
9	DRIVEWAY PROFILE
10	UTILITY PLAN (1)
11	UTILITY PLAN (2)
12	WASTEWATER DETAILS
13	WASTEWATER LEACHFIELD DETAILS
14	CONSTRUCTION DETAILS (1)
15	CONSTRUCTION DETAILS (2)
16	CONSTRUCTION DETAILS (3)
17	CONSTRUCTION DETAILS (4)
18	CONSTRUCTION DETAILS (5)
19	LANDSCAPE PLAN (1)
20	LANDSCAPE PLAN (2)
21	BACKYARD PLAN & DETAILS
22	PLANTING DETAILS

**GENERAL NOTES:** 

lan Set:

1. THIS PLAN SET IS FOR <u>PERMITTING ONLY</u> AND NOT FOR CONSTRUCTION.

2. SITE INFORMATION: ADDRESS: CAPE VIEW WAY

ZONING DISTRICT: R40

3. THE PROPERTY IS LOCATED WITHIN F.I.R.M. ZONE X AS SHOWN ON COMMUNITY PANEL NO. 25001C0316J DATED JULY 16, 2014.

4. THE WETLAND DELINEATION SHOWN HEREON WAS CONDUCTED BY HORSLEY WITTEN GROUP. SEE EXISTING CONDITIONS PLAN FOR DATES AND LOCATIONS OF WETLAND SURVEY

# CAPE VIEW WAY PERMITTING PLANS BOURNE, MASSACHUSETTS

Prepared For: PRESE		OLIV	Έ Ο	R S <sup>-</sup>	OF AFFORDABLE HO STREET, SUITE 500 FON, MA 02109 17) 261-9898	DUSING
Prepared By:			na	ble	y Witten Group, Inc. Environmental Solutions horsleywitten.com	
Headquarters 90 Route 6A Sandwich, MA 02563 (508) 833-6600 voice (508) 833-3150 fax		112 Water Bostor (857) 26	n, M/	A 02	109 Providence, RI 02906 (401) 272-1717 voice	113 Water Street, R2 Exeter, NH 03833 (603) 658-1660
Registration:	Re A		EW⊦	-	Revision per peer review comments	Project Number: 19038
RICHARD A. CLAYTOR CIVIL NO. 45116				-	Revised building location & total units Final revisions per ZBA comments	Sheet Number: 1 of 22
12-21-202-1	A Rev.	Date	Ву	Appr	Description	Drawing Number:

	ALL SITE WORK TO COMPLETE THIS PROJECT AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATIONS IS THE SOLE		OSION & SEDIMENT CONTROL NOT
	RESPONSIBILITY OF THE CONTRACTOR. IMMEDIATELY CONTACT AND COORDINATE WITH THE ENGINEER AND OWNER IF ANY DEVIATION OR ALTERATION OF THE WORK PROPOSED ON THESE DRAWINGS IS REQUIRED.	1.	PRIOR TO THE START OF CONSTRUCTION A NOTICE POLLUTION PREVENTION PLAN (SWPPP) REGARDIN ONSITE AT ALL TIMES. FOLLOW THE SWPPP PROTO THE SITE HAS BEEN ACCEPTED BY THE OWNER. A NOTICE OF TERMINATION WITH NPDES. IN ACCORD
3.	UTILIZE ALL PRECAUTIONS AND MEASURES TO ENSURE THE SAFETY OF THE PUBLIC, ALL PERSONNEL AND PROPERTY DURING CONSTRUCTION IN ACCORDANCE WITH OSHA STANDARDS, INCLUDING THE INSTALLATION OF TEMPORARY FENCING BARRICADES, SAFETY LIGHTING, CONES, POLICE DETAIL AND/OR FLAGMEN AS DETERMINED NECESSARY BY THE TOWN OF BOURNE. THE CONTRACTOR IS RESPONSIBLE FOR THE COST OF POLICE DETAIL AND FOR COORDINATING WITH THE LOCAL OR STATE POLICE DEPARTMENT FOR ALL REQUIRED POLICE DETAIL.	2.	THE SITE EROSION CONTROL DOCUMENTATION, W PERSONNEL, AND ANY OTHER PERTINENT SITE DO OF TERMINATION. DESIGNATE THE SITE CONSTRUCTION FOREMAN AS
4.	MAKE ALL NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN ALL NECESSARY CONSTRUCTION PERMITS, PAY ALL FEES INCLUDING POLICE DETAILS AND POST ALL BONDS, IF NECESSARY, ASSOCIATED WITH THE SAME, AND COORDINATE WITH THE OWNER AND THE ENGINEER.		MAINTENANCE OF ALL SEDIMENT AND EROSION CC EROSION AND PREVENT SEDIMENT FROM LEAVING INSTALL ALL EROSION AND SEDIMENT CONTROL (E
5.	ALL EXISTING CONDITIONS SHOWN ARE APPROXIMATE AND ARE BASED ON THE BEST INFORMATION AVAILABLE. PRIOR TO THE START CONSTRUCTION VERIFY THAT THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS DO NOT CONFLICT WITH ANY KNOWN EXISTING OR OTHER PROPOSED IMPROVEMENTS. IF ANY CONFLICTS ARE DISCOVERED, NOTIFY THE OWNER AND THE ENGINEER PRIOR TO INSTALLING ANY PORTION OF THE SITE WORK WHICH WOULD BE AFFECTED.	0.	CONSERVATION AGENT, AND ENGINEER BEFORE A EROSION CONTROL MEASURES, AS NECESSARY, D PERIMETER EROSION CONTROLS ARE THE DESIGN THAT NO CONSTRUCTION ACTIVITY IS TO OCCUR B PERIOD.
6.	THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS INDICATED ON THE DRAWINGS ARE BASED ON RECORDS OF VARIOUS UTILITY COMPANIES, AND WHEREVER POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES IN THE FIELD PRIOR TO THE START OF CONSTRUCTION. CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY IN		MAINTAIN A MINIMUM SURPLUS OF 100 FEET OF EF ALL TIMES. PROTECT THE ADJACENT RESOURCE AREA FROM S
	THE TOWN OF BOURNE, AND "DIGSAFE" (1-888-344-7233) AT LEAST THREE BUSINESS DAYS PRIOR TO ANY EXCAVATION WORK IN PREVIOUSLY UNALTERED AREAS TO REQUEST EXACT FIELD LOCATION OF UTILITIES. THE CONTRACTOR MUST RESOLVE CONFLICTS BETWEEN THE PROPOSED UTILITIES AND FIELD-LOCATED UTILITIES AND REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR DAMAGES INCURRED AS A RESULT OF UTILITIES OMITTED, INCOMPLETELY OR	6.	OWNER & IN CONFORMANCE WITH THE ORDER OF PROVIDE CONSTRUCTION EXITS AS INDICATED ON REPLACE THE CRUSHED STONE PAD, AS NECESSAI
7.	INACCURATELY SHOWN. THE CONTRACTOR MUST MAINTAIN ACCURATE RECORDS OF THE LOCATION AND ELEVATION OF ALL WORK INSTALLED AND EXISTING UTILITIES FOUND DURING CONSTRUCTION FOR THE PREPARATION OF THE AS-BUILT PLAN. COORDINATE AND MAKE ALL CONNECTION ARRANGEMENTS WITH UTILITY COMPANIES, AS REQUIRED.	7.	KEEP THE LIMIT OF CLEARING, GRADING AND DISTUPHASE THE SITE WORK IN A MANNER TO MINIMIZE AND GRUB ONLY THOSE AREAS WHICH ARE ACTIVE
8.	THE CONTRACTOR MUST MAINTAIN ALL EXISTING UTILITIES IN WORKING ORDER AND FREE FROM DAMAGE DURING THE ENTIRE DURATION OF THE PROJECT. REPAIR ANY DAMAGE TO EXISTING UTILITY LINES OR STRUCTURES INCURRED DURING CONSTRUCTION OPERATIONS AT NO COST TO THE OWNER. THE CONTRACTOR IS RESPONSIBLE FOR ALL COST RELATED TO THE REPAIR OF UTILITIES. EXCAVATION REQUIRED WITHIN THE PROXIMITY OF EXISTING UTILITY LINES MUST BE DONE BY HAND.	8.	PRIOR TO BEGINNING ANY LAND CLEARING ACTIVIT MONITOR LOCAL WEATHER REPORTS DURING CON CONSTRUCTION ACTIVITIES WHICH LEAVE LARGE BEST PROFESSIONAL JUDGEMENT AND GOOD CON ENSURE THE NECESSARY EROSION CONTROL DEV
9.	COORDINATE ALL TRENCHING WORK WITHIN ROADWAYS WITH THE PROPER LOCAL & STATE AGENCY. THE CONTRACTOR IS RESPONSIBLE FOR ALL TRENCH SAFETY INCLUDING ANY LOCAL AND/OR STATE PERMITS REQUIRED FOR THE TRENCH WORK. IF THIS WORK IS REQUIRED TO OCCUR OUTSIDE THE AGREED UPON HOURS OF OPERATION FOR THE FACILITY, THE CONTRACTOR MUST PLAN ACCORDINGLY.	9.	ANY IMPENDING WEATHER EVENTS. INSPECT EROSION AND SEDIMENT CONTROL DEVIC EVENT OF .25 INCH OR GREATER. REPAIR IDENTIF ARE IN GOOD WORKING ORDER. RESET OR REPLA
10.	SAWCUT ALL TRENCH WORK WITHIN EXISTING PAVEMENT AS INDICATED ON THE DRAWINGS. BACKFILL AND COMPACT TRENCH WORK AS INDICATED ON THE DRAWING AND IN THE SPECIFICATIONS. IF SETTLEMENT OCCURS DUE TO INADEQUATE COMPACTION, AS DETERMINED BY THE ENGINEER, WITHIN THE WARRANTY PERIOD, CONTRACTOR IS REQUIRED TO REMOVE, PATCH AND REPAVE AFTER	10.	SURROUND THE PERIMETER OF SOIL STOCKPILES WITH STRAWBALE, AS DETERMINED NECESSARY.
	ONE COMPLETE 12-MONTH CYCLE. IMPORT ONLY CLEAN MATERIAL. MATERIAL FROM AN EXISTING OR FORMER 21E SITE AS DEFINED BY THE MASSACHUSETTS CONTINGENCY PLAN 310 CMR 40.0000 WILL NOT BE ACCEPTED . IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH AND MAINTAIN ALL CONTROL POINTS AND BENCHMARKS DURING	11.	DISTURBED AREAS AND SLOPES MUST NOT BE LEF INACTIVE WINTER SEASON. PROVIDE APPROPRIAT BUT NOT MORE THAN 14 DAYS AFTER THE CONSTR REINFORCE TEMPORARY AREAS HAVING A SLOPE SITE IS PROPERLY STABILIZED. TEMPORARY SWAL
	CONSTRUCTION INCLUDING BENCHMARK LOCATIONS AND ELEVATIONS AT CRITICAL AREAS. COORDINATE WITH THE ENGINEER THE LOCATION OF ALL CONTROL POINTS AND BENCHMARKS. SITE LAYOUT SURVEY REQUIRED FOR CONSTRUCTION MUST BE PROVIDED BY THE CONTRACTOR AND PERFORMED BY A	12.	ENGINEER. INSTALL A SILT SACK OR APPROVED EQUIVALENT II INSTALLATION OF EACH CATCH BASIN, INSTALL A S
	MASSACHUSETTS' REGISTERED PROFESSIONAL LAND SURVEYOR. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH THE SURVEYOR FOR ALL SITE SURVEY WORK. MAINTAIN ALL GRADE STAKES SET BY THE SURVEYOR. GRADE STAKES ARE TO REMAIN UNTIL A FINAL INSPECTION OF THE ITEM HAS	13.	SIGNIFICANT STORM EVENT AND REMOVE AND EMP SMALL SEDIMENTATION BASINS MAY BE CONSTRUCT OF SITE RUNOFF AND SEDIMENT. IT WILL BE THE R
	BEEN COMPLETED BY THE ENGINEER. RE-STAKING OF PREVIOUSLY SURVEYED SITE FEATURES IS THE RESPONSIBILITY (INCLUDING COST) OF THE CONTRACTOR. UNLESS OTHERWISE INDICATED ON THE DRAWINGS AND/OR IN THE SPECIFICATIONS, ALL SITE CONSTRUCTION MATERIALS AND	14.	ENGINEER, TO SIZE AND CREATE THESE BASINS IN CONTAIN ALL SEDIMENT ONSITE. SWEEP ALL EXITS PAVED AREAS AS NEEDED TO REMOVE SEDIMENT
	METHODOLOGIES ARE TO CONFORM TO THE MOST RECENT VERSION OF THE MASSACHUSETTS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS (THE COMMONWEALTH OF MASSACHUSETTS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGES 2020 EDITION).		BEMOVE ACCUMULATED SEDIMENT FROM ALL TEM
	PROVIDE ALL CONSTRUCTION SERVICE IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS REGARDING NOISE, VIBRATION, DUST, SEDIMENTATION CONTAINMENT, AND TRENCH WORK.		PROVIDE ON SITE OR MAKE READILY AVAILABLE TH
	COLLECT SOLID WASTES AND STORE IN A SECURED DUMPSTER. THE DUMPSTER MUST MEET ALL LOCAL AND STATE SOLID WASTE MANAGEMENT REGULATIONS. RESTORE ALL SURFACES EQUAL TO THEIR ORIGINAL CONDITION AFTER CONSTRUCTION IS COMPLETE PER SPECIFICATIONS. LEAVE ALL		MAINTAINED AND REPAIRED IN A TIMELY AND RESP THE CONTRACTOR MUST CONTINUE TO PROPERLY MAINTAIN AND REPAIR ALL EROSION AN
19.	AREAS NOT DISTURBED BY CONSTRUCTION IN THEIR NATURAL STATE. TAKE CARE TO PREVENT DAMAGE TO SHRUBS, TREES, OTHER LANDSCAPING AND/OR NATURAL FEATURES. WHEREAS THE PLANS DO NOT SHOW ALL LANDSCAPE FEATURES, EXISTING CONDITIONS MUST BE VERIFIED BY THE CONTRACTOR IN ADVANCE OF THE WORK. REGULARLY INSPECT THE PERIMETER OF THE PROPERTY TO CLEAN UP AND REMOVE LOOSE CONSTRUCTION DEBRIS BEFORE IT LEAVES	18.	PRIOR TO THE INSTALLATION OF FILTER FABRIC AN OF SEDIMENT ACCUMULATED IN ANY PARTIALLY CO SEDIMENT CONTROL DURING CONSTRUCTION. PRO MEDIA ELEVATION AS SHOWN IN THE BIORETENTION ALLOWS FOR AN OVER-DIG OF THE COLLECTED SE
20.	THE SITE. PROMPTLY REMOVE ALL DEMOLITION DEBRIS FROM THE SITE TO AN APPROVED DUMP SITE. ALL TRUCKS LEAVING THE SITE MUST BE COVERED.	19.	INSTALLATION. CONTROL DUST BY WATERING OR OTHER APPROV
	DO NOT WASH ANY CONCRETE TRUCKS ONSITE. REMOVE BY HAND ANY CEMENT OR CONCRETE DEBRIS LEFT IN THE DISTURBED AREA. BURIAL OF ANY STUMPS, SOLID DEBRIS, AND/OR STONES/BOULDERS ONSITE IS PROHIBITED. DO NOT USE ROAD SALT OR OTHER DE-ICING CHEMICALS ON THE ACCESS ROADWAY.	20.	THE CONTRACTOR IS RESPONSIBLE FOR THE INSP FACILITIES INSTALLED OR AFFECTED BY THE PROJ THE PROJECT WORK PRIOR TO THE OWNER'S ACCI
	AT THE END OF CONSTRUCTION, REMOVE ALL CONSTRUCTION DEBRIS AND SURPLUS MATERIALS FROM THE SITE [AS INDICATED IN THE SPECIFICATIONS]. PERFORM A THOROUGH INSPECTION OF THE WORK PERIMETER. COLLECT AND REMOVE ALL MATERIALS AND BLOWN OR WATER CARRIED DEBRIS FROM THE SITE.		
	FOLLOWING CONSTRUCTION SEQUENCE IS TO BE USED AS A GENERAL GUIDELINE. COORDINATE WITH THE OWNER, ENGINEERS, AND DSCAPE ARCHITECT AND SUBMIT A PROPOSED CONSTRUCTION SEQUENCE FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.		
	SURVEY AND STAKE THE PROPOSED LIMIT OF DISTURBANCE AND LIMIT OF SEDIMENTATION BARRIERS.		
	IDENTIFY AND MARK INVASIVE SPECIES. PLANT IDENTIFICATION SHALL BE PERFORMED BY QUALIFIED PERSONNEL ONLY, AS INDICATED IN THE SPECIFICATIONS. PLACE SEDIMENTATION BARRIERS AND INLET PROTECTION AS INDICATED ON DRAWINGS AND STAKED OUT IN THE FIELD. UNDER NO CIRCUMSTANCES IS THE LIMIT OF WORK TO EXTEND BEYOND THE SEDIMENTATION BARRIERS/LIMIT OF DISTURBANCE AS INDICATED ON		
4.	DRAWINGS AS APPROVED BY THE LOCAL CONSERVATION COMMISSION AND DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP). PROTECT ALL SUBSURFACE INFILTRATION STRUCTURES FROM FLOW UNTIL SITE IS STABILIZED. INSTALL TEMPORARY CONSTRUCTION ENTRANCES IN LOCATIONS INDICATED ON DRAWINGS. NO OTHER ENTRANCES ARE TO BE USED		
4. 5.	TO GAIN ACCESS TO THE SITE BY ANY CONSTRUCTION OR DELIVERY VEHICLES. BEGIN CLEARING THE SITE AS REQUIRED. SEE SPECIFICATIONS FOR INVASIVE SPECIES MANAGEMENT.		
6.	SURVEY AND STAKE CENTERLINE OF THE PROPOSED ROADS, STORMWATER MANAGEMENT AREAS, AND DRAINAGE LINES.		
1.	EXCAVATE AND ROUGH GRADE THE PROPOSED STORMWATER MANAGEMENT AREAS AND ANY ADDITIONAL TEMPORARY BASINS NECESSARY TO CONTROL SITE RUNOFF AND SEDIMENT. TEMPORARILY STABILIZE/SEED PERMANENT STORMWATER MANAGEMENT AREAS AS NECESSARY TO REDUCE SIDE SLOPE EROSION AND SEDIMENT ACCUMULATION.		
8.	BEGIN CLEARING AND GRUBBING THE AREAS OF ROADWAYS AND STORMWATER MANAGEMENT AREAS. TOPSOIL IS TO BE STRIPPED FROM THE AREA OF THE PROPOSED ROADWAYS AND STORMWATER MANAGEMENT AREAS AND STOCKPILED IN APPROVED LOCATIONS. TOPSOIL STOCKPILES MUST BE PROTECTED BY A SEDIMENT BARRIER.		
	INSTALL TEMPORARY CONVEYANCE DEVICES (SWALES, CHECK DAMS, PIPES, ETC.) AS NECESSARY TO CONVEY RUNOFF TO TREATMENT AREAS. BEGIN ROUGH GRADING AREAS FOR ROADS, PARKING AND BUILDINGS. BRING ROUGH GRADING TO PROPER ELEVATIONS AS SOON AS		
	PRACTICABLE. COORDINATE WORK TO MINIMIZE TIME SOILS ARE UN-STABILIZED. BEGIN UTILITY CONSTRUCTION. THE CONTRACTOR IS FREE TO INSTALL THE UTILITIES IN THE SEQUENCE HE/SHE CHOOSES.		
12.	IMMEDIATELY REPAIR, REPLACE AND STABILIZE ANY EROSION CONTROL DEVICES DISTURBED DURING THE UNDERGROUND UTILITY CONSTRUCTION. MODIFY TEMPORARY CONVEYANCE DEVICES, AS NECESSARY, TO CONVEY RUNOFF TO TREATMENT AREAS. INSTALL DRAINAGE PIPES, DRAINAGE MANHOLES, CATCH BASINS, AND UNDERGROUND DRAINAGE STRUCTURES. BEGIN WORK AT THE		
13	STORMWATER MANAGEMENT AREAS AND PROGRESS UP-GRADIENT. PROTECT DISCHARGE OUTLETS WITH RIP-RAP APRONS. THE STORMWATER MANAGEMENT AREA(S) AND DRAINAGE NETWORK ARE TO BE PROTECTED FROM SEDIMENTATION UNTIL ALL UN-STABILIZED AREAS ARE STABILIZED WITH STONE SUB-BASE OR VEGETATION. INSTALL SEDIMENT BARRIERS AT ALL POINTS OF ENTRY INTO THE DRAINAGE NETWORK. TAKE PARTICULAR CARE TO PROTECT THE UNDERGROUND STRUCTURES FROM SEDIMENT. PERMANENTLY SEED ALL DISTURBED AREAS OUTSIDE OF THE AREA TO BE PAVED.		Δ
	UPON COMPLETION OF UNDERGROUND UTILITIES INSTALLATION, PLACE COMPACTED GRAVEL FOUNDATION AND ROUGH GRADE THE ROADWAYS/PARKING AREAS IN ACCORDANCE WITH THE SITE PLANS AND IN ACCORDANCE WITH APPLICABLE STATE AND LOCAL REGULATIONS AS SOON AS POSSIBLE.		
15.	BEGIN ROAD AND PARKING CONSTRUCTION PER SITE PLANS AND IN ACCORDANCE WITH APPLICABLE STATE AND LOCAL REGULATIONS. ROADS AND PARKING AREAS ARE NOT TO BE PAVED UNTIL THE ENTIRE PERMANENT DRAINAGE SYSTEM HAS BEEN INSTALLED AND ALL PIPE CONNECTIONS COMPLETE.		
	FINISH PERMANENT STABILIZATION. COMPLETE PERMANENT STORMWATER MANAGEMENT AREA SEEDING AND PLANTING AFTER THE CONTRIBUTING AREA TO THE BASIN HAS REACHED A MINIMUM OF 80% STABILIZATION AND IS NO LONGER REQUIRED AS A CONSTRUCTION SEDIMENTATION BASIN. COMPLETE ALL REMAINING PLANTING AND SEEDING.		
	SWEEP THE ROADWAY TO REMOVE ALL SEDIMENTS. REPAIR DRAINAGE OUTLETS AND BASINS AS REQUIRED. CLEAN AND FLUSH THE DRAINAGE STRUCTURES AND PIPES AT THE END OF CONSTRUCTION AND REMOVE ALL ACCUMULATED SEDIMENTS IN THE STORMWATER MANAGEMENT AREAS. CONTRACTOR MUST INSPECT THE DRAINAGE NETWORK AND REPAIR ANY DAMAGE IMMEDIATELY.		
17.	ENGINEER TO APPROVE THE REMOVAL OF ALL TEMPORARY SOIL EROSION AND SEDIMENTATION CONTROL MEASURES FOLLOWING VEGETATIVE ESTABLISHMENT OF ALL DISTURBED AREAS AND DETERMINE WHEN THE CONTRIBUTING AREA HAS REACHED A MINIMUM OF 80% STABILIZATION.		

### OL NOTES:

STORMWATER FACILITY OPERATION & MAINTENANCE:

N A NOTICE OF INTENT (NOI) MUST BE FILED WITH NPDES. REFER TO THE STORMWATER AND REGARDING ALL EROSION CONTROL MATTERS. MAINTAIN A WORKING COPY OF THE SWPPP PPP PROTOCOL FOR SITE MAINTENANCE. INSPECTIONS AND PROPER DOCUMENTATION UNTIL DWNER. AT THE COMPLETION OF THE PROJECT THE CONTRACTOR OR OWNER MUST FILE A IN ACCORDANCE WITH NPDES REGULATIONS, THE COMPLETED SWPPP MUST INCLUDE ALL OF TATION, WEEKLY EROSION INSPECTION REPORTS COMPLETED BY THE DESIGNATED SITE IT SITE DOCUMENTATION MUST BE RETAINED FOR A MINIMUM OF 3 YEARS FROM THE DATE

DREMAN AS THE ON-SITE PERSONNEL RESPONSIBLE FOR THE DAILY INSPECTION AND ROSION CONTROLS AND IMPLEMENTATION OF ALL NECESSARY MEASURES TO CONTROL M LEAVING THE SITE.

ONTROL (ESC) MEASURES AS INDICATED ON DRAWINGS IN CONSULTATION WITH THE BEFORE ANY CONSTRUCTION ACTIVITIES BEGIN. INSPECT, MAINTAIN REPAIR AND REPLACE ESSARY, DURING THE ENTIRE CONSTRUCTION PERIOD OF THE PROJECT. THE SITE HE DESIGNATED LIMIT OF WORK. INFORM ALL PERSONNEL WORKING ON THE PROJECT SITE OCCUR BEYOND THE LIMIT OF WORK AT ANY TIME THROUGHOUT THE CONSTRUCTION

EET OF EROSION CONTROL BARRIER (SILT FENCE, STRAWBALE, &/OR SILT SOCK) ONSITE AT

EA FROM SEDIMENTATION DURING PROJECT CONSTRUCTION UNTIL ACCEPTANCE BY THE ORDER OF CONDITIONS. CATED ON DRAWINGS TO SHED DIRT FROM CONSTRUCTION VEHICLE TIRES. CLEAN AND/OR NECESSARY, TO MAINTAIN ITS EFFECTIVENESS.

AND DISTURBANCES TO A MINIMUM WITHIN THE PROPOSED AREA OF CONSTRUCTION. MINIMIZE AREAS OF EXPOSED SOIL. IF TREES ARE TO BE CUT ON THE ENTIRE SITE, CLEAR ARE ACTIVELY UNDER CONSTRUCTION. PROPERLY INSTALL THE SEDIMENTATION CONTROLS NG ACTIVITY AND/OR OTHER CONSTRUCTION RELATED WORK.

IRING CONSTRUCTION AND PRIOR TO SCHEDULING EARTHMOVING OR OTHER VE LARGE DISTURBED AREAS UNSTABILIZED. IF INCLEMENT WEATHER IS PREDICTED, USE GOOD CONSTRUCTION PRACTICES WHEN SCHEDULING CONSTRUCTION ACTIVITIES AND ITROL DEVICES ARE INSTALLED AND FUNCTIONING PROPERLY TO MINIMIZE EROSION FROM

ROL DEVICES AND STABILIZED SLOPES ON A WEEKLY BASIS AND AFTER EACH RAINFALL IR IDENTIFIED PROBLEMS WITHIN 24 HOURS TO ENSURE EROSION AND SEDIMENT CONTROLS OR REPLACE MATERIALS AS REQUIRED. OCKPILES WITH SILT SOCK, SILT FENCE, STRAWBALES, OR A COMBINATION OF SILT FENCE

OT BE LEFT UNATTENDED OR EXPOSED FOR EXCESSIVE PERIODS OF TIME SUCH AS THE PROPRIATE STABILIZATION PRACTICES ON ALL DISTURBED AREAS AS SOON AS POSSIBLE E CONSTRUCTION ACTIVITY IN THAT AREA HAS TEMPORARILY OR PERMANENTLY CEASED, A SLOPE GREATER THAN 4:1 WITH EROSION BLANKETS OR APPROVED EQUAL UNTIL THE ARY SWALES MAY ALSO BE REQUIRED IF DETERMINED NECESSARY IN THE FIELD BY THE

JIVALENT IN EACH EXISTING CATCHBASIN RECEIVING RUNOFF FROM THE SITE. UPON THE ISTALL A SILT SACK OR APPROVED EQUIVALENT. INSPECT SILT SACKS, AFTER EACH E AND EMPTY AS NEEDED FOR THE DURATION OF THE CONSTRUCTION PERIOD.

CONSTRUCTED ON AN AS-NEEDED BASIS DURING CONSTRUCTION TO AID IN THE CAPTURE L BE THE RESPONSIBILITY OF THE SITE CONTRACTOR, IN CONSULTATION WITH THE BASINS IN APPROPRIATE LOCATIONS.

PALL EXITS FROM THE SITE AS NECESSARY INCLUDING ANY SEDIMENT TRACKING. SWEEP SEDIMENT AND POTENTIAL POLLUTANTS ACCUMULATED DURING SITE CONSTRUCTION.

MAL TEMPORARY PRACTICES AND DISPOSE OF IN A PRE-APPROVED LOCATION. CATCH BASINS.

AILABLE THE NECESSARY EQUIPMENT AND SITE PERSONNEL DURING CONSTRUCTION HOURS ENSURE ALL EROSION AND SEDIMENTATION CONTROL DEVICES ARE PROPERLY AND RESPONSIBLE MANNER. IF SITE WORK IS SUSPENDED DURING THE WINTER MONTHS PROVIDE PERSONNEL AND EQUIPMENT FITHER ON SITE OR READILY AVAILABLE TO ROSION AND SEDIMENTATION CONTROL DEVICES IN A TIMELY AND RESPONSIBLE MANNER

FABRIC AND MEDIA WITHIN THE BIORETENTION AREAS, REMOVE AND PROPERLY DISPOSE RTIALLY CONSTRUCTED OR TEMPORARY BIORETENTION/DRAINAGE AREA USED FOR CTION. PROVIDE A SURFACE ELEVATION AT A MINIMUM 1-FOOT ABOVE THE BOTTOM OF RETENTION SCHEDULE FOR PARTIALLY CONSTRUCTED BIORETENTION AREAS. THIS ECTED SEDIMENT FROM WITHIN THE BIORETENTION AREA PRIOR TO MEDIA/FABRIC

R APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE ENGINEER.

THE INSPECTION AND MAINTENANCE DURING CONSTRUCTION OF ALL STORMWATER THE PROJECT. REMOVE SEDIMENT OR DEBRIS COLLECTED WITHIN THESE FACILITIES FROM NER'S ACCEPTANCE.

- THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER INSPECTION AND MAINTENANCE OF ALL STORMWATER MANAGEMENT FACILITIES AS OUTLINED BELOW DURING CONSTRUCTION AND UNTIL SUCH TIME THAT THE ROADWAYS AND ASSOCIATED UTILITIES ARE ACCEPTED BY THE OWNER AND THE ENGINEER.
- INSPECT AND RESTORE/CLEAN ALL FACILITIES (INLETS, MANHOLES, INFILTRATION BASINS, STORMWATER MANAGEMENT AREAS AS DESCRIBED BELOW OF SEDIMENT AND DEBRIS PRIOR TO THE OWNER'S ACCEPTANCE.
- REMOVE AND DISPOSE ALL SEDIMENT AND DEBRIS TO A PRE-APPROVED LOCATION.
- 3. REFER TO THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) FOR ADDITIONAL INFORMATION PERTAINING TO STORMWATER FACILITY OPERATION AND MAINTENANCE REQUIREMENTS. MAINTAIN A WORKING COPY OF THE SWPPP ON SITE AT ALL TIMES. AT A MINIMUM INSPECT MONTHLY AND AFTER STORM EVENTS GREATER THAN OR EQUAL TO 1" OF RAINFALL AS NECESSARY FOR THE 4
- ENTIRE DURATION OF THE CONSTRUCTION PROJECT AND THE FIRST 3 MONTHS AFTER CONSTRUCTION TO ENSURE PROPER STABILIZATION. SPECIFIC MAINTENANCE REQUIRED DURING CONSTRUCTION:
- A. DRAINAGE STRUCTURES (INLETS, MANHOLES, CATCHBASINS): MONITOR AND REGULARLY INSPECT ALL EXISTING AND PROPOSED DRAINAGE STRUCTURES FOR PROPER OPERATION, COLLECTION OF LITTER OR TRASH, AND STRUCTURAL DETERIORATION. CLEAN AND REMOVE SEDIMENT FRO THE STRUCTURES (INCLUDING SUMPS) AS NECESSARY, AND REPAIR WHEN REQUIRED.
- B. SEDIMENT FOREBAY: REGULARLY INSPECT TO ENSURE PROPER FUNCTION. REMOVE SEDIMENT BUILD-UP ON THE FLOOR OF THE FOREBAY AND PROPERLY DISPOSE, AS NECESSARY, TO LIMIT CLOGGING. CLEAN SEDIMENT FOREBAYS PRIOR TO COMPLETION OF CONSTRUCTION.
- C. BIORETENTION SYSTEMS: REGULARLY INSPECT TO ENSURE PROPER FUNCTION. MONITOR AND INSPECT STRUCTURAL COMPONENTS, INCLUDING WEIR WALLS, DRAINAGE INLETS, OUTLET STRUCTURES AND SPILLWAYS, FOR PROPER FUNCTION. CLEAN AND REPAIR ANY CLOGGED STRUCTURES DURING INSPECTIONS. PRIOR TO THE COMPLETION OF CONSTRUCTION, REMOVE AND REPLACE ILL-ESTABLISHED, DEAD OR SEVERELY DISEASED PLANTS, REMOVE SEDIMENT BUILD-UP AS NEEDED, AND REPLACE SOIL WHEN NECESSARY. IF SEDIMENT OR ORGANIC DEBRIS BUILD-UP LIMITS THE INFILTRATION CAPABILITIES, REMOVE THE TOP 6" OR GREATER AND SURFACE ROTO-TILLED TO A DEPTH OF 12".
- ROUTINE MAINTENANCE: OTHER ROUTINE MAINTENANCE INCLUDES THE REMOVAL OF TRASH AND LITTER FROM PAVED AND PERIMETER AREAS, AND STREET AND PARKING LOT SWEEPING UPON COMPLETION OF CONSTRUCTION TO AVOID EXCESSIVE ACCUMULATION OF SEDIMENT IN THE DRAINAGE SYSTEM. INSPECT THE PIPES AND STRUCTURES FOR SEDIMENT ACCUMULATION AND PROPER FLOW.

### WATER & SEWER INSTALLATION NOTES

5.

1. INSTALL SEWER AND WATER MAINS ACCORDING TO THE FOLLOWING GUIDELINES TO PREVENT FREEZING OF THE MAIN OR SEWER:

	MIN. COVER OVER TOP OF PIPE	MIN. HORIZONTAL DISTANCE TO DRAIN STRUCTURE
SANITARY FORCEMAIN	5'	3'
GRAVITY FORCEMAIN	4'	2'
WATER MAIN	5'	2'

- INSULATE SANITARY FORCE MAINS, WATER MAINS, HYDRANT PIPING AND DEAD END WATER LINES S WHERE SOIL COVER OR HORIZONTAL SEPARATION TO PRECAST STRUCTURES IS LESS THAN THE DISTANCE SPECIFIED ABOVE AND/OR WHERE SHOWN ON PLANS.
- INSULATION: 2" THICK POLYURETHANE INSULATION WITH PVC JACKET PLACED AROUND PIPE OR DESIGNER APPROVED EQUAL. WATER AND SEWER SEPARATION IS TYPICALLY 10-FEET MINIMUM HORIZONTAL AND 18-INCHES VERTICAL WITH SEWER MAINS BELOW THE WATER MAINS (SEE DETAIL). IF SITE CONDITIONS REQUIRE LESS, THEN INSTALL UTILITIES AS INDICATED ON DETAILS.

### WATER SYSTEM INSTALLATION NOTES

- CONSTRUCT THE WATER MAIN AND ITS APPURTENANCE IN ACCORDANCE WITH THE LOCAL WATER DEPARTMENT'S STANDARDS AND SPECIFICATIONS AND PAY FOR ALL ASSOCIATED FEES AS REQUIRED BY THE WATER DEPARTMENT.
- 2. ALL PROPOSED WATER MAIN 4-INCHES AND GREATER IN DIAMETER ARE DUCTILE IRON CLASS 52. ONLY USE HDPE 3408 OR AS INDICATED ON DRAWINGS OR AS APPROVED BY THE ENGINEER.
- SUPPLY TWO COPIES OF SWORN CERTIFICATES TO PROVE THAT ALL PIPES AND FITTINGS ARE INSPECTED AND TESTED AS REQUIRED BY THE STANDARD SPECIFICATIONS TO WHICH THE MATERIAL IS MANUFACTURED.
- GATE VALVES: MUELLER (A 2360 SERIES), CLOW (AWWA STANDARD C509 SERIES), AMERICAN DARLING (RESILIENT WEDGE) OR APPROVED EQUAL
- PROVIDE GATE VALVES ON ALL HYDRANT BRANCHES AND WATER MAIN. THE GATE VALVE TO TURN TO THE RIGHT TO OPEN (CLOCKWISE). ALL BOLTS AND NUTS MUST BE RUST PROOF STEEL.
- CLEAR ALL NEWLY INSTALLED WATER SYSTEM COMPONENTS OF ALL FOREIGN MATERIALS SUCH AS DIRT AND MISCELLANEOUS DEBRIS PRIOR 6. TO SYSTEM TESTING . NO TESTING IS ALLOWED WITHOUT REMOVAL OF ALL FOREIGN MATERIALS.
- CONTRACTOR IS RESPONSIBLE FOR CONDUCTING A PRESSURE TEST AND DISINFECTION TEST OF ALL WATER MAINS. THE TESTS MUST WITNESSED BY THE APPROVED INSPECTOR OR THE ENGINEER. THE CONTRACTOR MUST PROVIDE A MINIMUM OF 48-HOUR ADVANCE NOTICE TO THE LOCAL WATER DEPARTMENT PRIOR TO THE PRESSURE AND DISINFECTION TESTS. THE CONTRACTOR MUST PROVIDE ALL NECESSARY EQUIPMENT AND CHEMICALS TO PROPERLY CONDUCT THE TESTS.
- 8. INSTALL AND REMOVE ALL NECESSARY BLOWOFFS REQUIRED FOR THIS PROJECT AT NO EXTRA COST TO THE OWNER.
- 9. COLLECT ALL BACTERIOLOGICAL SAMPLES AND PAY FOR ALL RELATED LABORATORY FEES.
- 10. MAINTAIN UP-TO-DATE AS-BUILT DRAWINGS AND NOTES INDICATING THE HORIZONTAL AND VERTICAL LOCATION WITH TWO TIES OF ALL SYSTEM COMPONENTS INSTALLED. AS-BUILT DRAWINGS AND NOTES WILL BE UTILIZED BY THE ENGINEER FOR THE PREPARATION OF RECORD PLANS.

### SEWER SYSTEM OPERATION & MAINTENANCE:

- CLEAN ALL NEWLY INSTALLED FACILITIES, INCLUDING SEWER COLLECTION SYSTEM OF ALL FOREIGN MATERIALS SUCH AS DIRT AND MISCELLANEOUS DEBRIS PRIOR TO SYSTEM TESTING. TESTING MUST BE WITNESSED AND INSPECTED BY THE ENGINEER. NO TESTING IS ALLOWED WITHOUT REMOVAL OF ALL FOREIGN MATERIALS.
- 2. CONDUCT A LEAKAGE TEST OF ALL SEWER MAINS. TEST MUST BE WITNESSED BY THE ENGINEER. THE CONTRACTOR MUST PROVIDE THE ENGINEER WITH A MINIMUM OF 48-HOURS ADVANCE NOTICE TO THE TIME OF THE PRESSURE TEST.
- 3. TEST SEWER PIPES FOR LEAKAGE WITH THE FOLLOWING PROCEDURE. INTRODUCE LOW PRESSURE AIR INTO THE SEAL LINE (WITH PNEUMATIC PLUGS) UNTIL THE INTERNAL AIR PRESSURE REACHES 4 psi GREATER THAN THE AVERAGE BACK PRESSURE OF ANY GROUNDWATER THAT MAY BE OVER THE PIPE. ALLOW AT LEAST 2 MINUTES FOR AIR PRESSURE TO STABILIZE. AFTER THE STABILIZATION PERIOD (3.5 psi MINIMUM PRESSURE IN THE PIPE), THE PORTION OF PIPE TESTED IS ACCEPTABLE IF THE TIME REQUIRED IN MINUTES FOR THE PRESSURE TO DECREASE FROM 3.5 TO 3 psi IS NOT LESS THAN 1.90 TIMES THE LENGTH OF PIPE BEING TESTED.
- 4. VACUUM TEST ALL SEWER MANHOLES. TESTS MUST BE WITNESSED BY THE ENGINEER UNLESS THE SEASONAL GROUNDWATER LEVEL IS MORE THAN 10 FEET FROM THE BOTTOM OF THE MANHOLE
- 5. MANDREL TEST ALL SEWER MAINS AFTER 30 DAYS. TESTS MUST BE WITNESSED BY A TOWN REPRESENTATIVE OR THE ENGINEER.


GENERAL			SYMBOLS	k com	
	BUILDING CENTERLINE		BENCHMARK	Revision per peer review comments	
44	CONTOUR - MINOR	CB	BOUNDARY	u ber	
50	CONTOUR - MAJOR CURB	$\triangle$	CONTROL POINT		
	CURB CUT	+ EL:95.00	SPOT GRADE	H BRK	
o	EDGE OF PAVEMENT FENCE - CHAIN LINK		SEWER MANHOLE	Revisions	
— x — _ x —	FENCE - WIRE		DRAIN MANHOLE	evis	
	LIMIT OF WORK PATHWAY		CATCHBASIN	ଝ୍ୟଶ୍ୟଶ୍	
	SIDEWALK STORMWATER AREA	$\bigtriangledown$	INLET PROTECTION		Checked By:
	TREE LINE	WV	WATER VALVE		Che
	WALL - RETAINING WALL - STONE	SV	SEWER VALVE	ls.	n By:
	CONCRETE	CS ●	CURB STOP	p, Ir	Drawn By:
	CROSSWALK/PAVEMENT STRIPING	CO ()	CLEAN OUT	<b>Group, Inc</b> . ental Solutions <i>m</i>	ined By:
PROPERTY INFORMATION			PIPE STUB		Designed By:
	ABUTTING LOT EASEMENT LINE	▼	THRUST BLOCK	Vitte Envirc witter voice fax	
UTILITIES	PROPERTY, LOT, OR ROW	$\bowtie$	UTILITY BOX	Horsley Witten Group, Inc Sustainable Environmental Solutions www.horsleywitten.com 90 Route 6A Sandwich, MA 02563 508-833-6600 voice 508-833-3150 fax	
		$\sum_{y \in Y}$	HYDRANT	Orsl ustain ww.hc NRout 38-833 38-833	Date:
	DRAIN PIPE SANITARY SEWER	¢	LIGHT POST	Ϋ́Ϋ́Ϋ́Ó́ÓÉÉÓ T	Da
UGE	UNDERGROUND ELEC.		TEST PIT		
EROSION & SEDIMENT CONTROL	WATER LINE	₽w	F WETLAND FLAG		
SF	SILT FENCE	$\bigcirc$	ROCK	ഗ	
ss	SILT SOCK	à	SIGN		ပ
ENVIRONMENTAL		<u>گر</u>	HANDICAP SYMBOL	AY ANS HUSE	
	WETLAND BOUNDARY	L	TRAFFIC DIRECTION	AA AA	Z
	WETLAND 50 BUFFER	▼		<ul><li>&lt; ⊑ </li></ul>	Z
	WETLAND 100 BUFFER				<u>○</u>
				CAPE VIEW WAY PERMITTING PLAN RNE, MASSACHUS	NSTRUCTION NOTES

# Ö m Ο (VATION ABLE ď,

# PERMITTING SET ONLY NOT FOR CONSTRUCTION

ject Numbe 19038 2 of 22 et Number C - 2


12-13-2021




	TP-D	
0"—	A	-61.0
	10 YR 4/2	
0"	SANDY LOAM	60.2
8"—	Bw	-60.3
	10 YR 5/8	
	SANDY LOAM	
40"—		57.7
40	C1	57.7
	10 YR 6/4	
0.0"	MEDIUM SAND	0
62"—	C2	-55.8
	10 YR 6/4	
	GRAVELLY FINE	
74"—	SAND	
	C3	04.0
	10 YR 6/4	
	FINE SAND	
120"—	NO GROUNDWATER	51.0
	OR REDOXIMORPHIC	
	FATURES OBSERVED	ר


DA	TE: OCTOBER 24, 207	19	DA	TE
	TP-6			
0"—	Α	-61.4	0"—	
12"—	10 YR 4/2 FINE SANDY LOAM	-60.4	22"—	F
12 —	Bw 10 YR 4/6	-00.4	22 —	
	SANDY LOAM		24"—	F
36"—	C1	-58.4		
	10 YR 6/3 GRAVELLY FINE		32"—	F
48"—	SAND	-57.4		
-0	C2 10 YR 6/3 MEDIUM SAND	57.4	38"—	
20"		-51.4	60"—	
	NO GROUNDWATER	01.4		NC
(	OR REDOXIMORPHIC		(	DF
F	EATURES OBSERVED	)	F	ΕA


0"	18-1
0 —	HTM
	10 YR 3/4
00"	FINE SANDY LOAM
22"—	Ab
	10 YR 4/6
24"—	FINE SANDY LOAM
24 —	Bw
	10 YR 6/6
201	FINE SANDY LOAM
32"—	C1
	10 YR 6/3
	GRAVELLY FINE
	SAND
38"—	
00	C2
	10 YR 6/3
	MEDIUM SAND
60"-	
00 -	





dified: 12/13/21 printed: 12/13/21 by eh K:\Projects\2019\19038 Cape View Way\Drawings\19038 S























### TYPICAL SYSTEM VENT DETAIL NOT TO SCALE

### WASTEWATER NOTES


- UNLESS OTHERWISE NOTED, ALL SYSTEM COMPONENTS AND CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH THE STATE ENVIRONMENTAL CODE AND THE RULES AND REGULATIONS OF THE LOCAL BOARD OF HEALTH.
- ANY CHANGES TO THIS PLAN MUST BE APPROVED BY THE ENGINEER AND/OR THE LOCAL BOARD OF HEALTH (BOH) STAFF.
- FAILING TO PROPERLY INSPECT OR PUMP THE SEPTIC TANKS AND TREATMENT SYSTEM OR CHANGES TO EFFLUENT FLOW, GRADING, OR LANDSCAPING, EITHER ON-SITE OR ADJACENT TO THE SITE, MAY RESULT IN IMPROPER FUNCTIONING OF THE SEPTIC AND LEACHING SYSTEM(S).
- 4. THIS ON-SITE WASTEWATER TREATMENT SYSTEM IS NOT DESIGNED FOR USE WITH GARBAGE GRINDERS.
- 5. THE OWNER SHALL INSPECT AND HAVE THE SEPTIC TANK PUMPED EVERY 2 YEARS.
- PROVIDE WATERTIGHT SEALS BY USE OF NON-SHRINK GROUT AT ALL POINTS WHERE PIPES ENTER OR LEAVE ANY CONCRETE STRUCTURES. 6.
- USE SCH. 40 PVC PIPING WITH WATERTIGHT JOINTS UNLESS OTHERWISE NOTED ON PLAN. ALL PIPE SHALL BE PLACED ON A COMPACTED FIRM BASE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONDUCTING A HYDROSTATIC PRESSURE TEST ON THE NEW SEWER FORCE MAIN. THE TEST SHALL CONSIST OF HOLDING A PRESSURE OF 50 PSI IN THE FORCE MAIN FOR A PERIOD OF 1 HOUR. THE TEST SHALL BE WITNESSED BY THE ENGINEER.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING OPERATIONS AND MAINTENANCE INFORMATION FOR THE SEPTIC SYSTEM TO THE ENGINEER. 9.
- 10. THE CONTRACTOR SHALL PROVIDE A DEWATERING PROTOCOL PRIOR TO CONSTRUCTION IF GROUNDWATER IS ANTICIPATED DURING CONSTRUCTION. AREAS UNDER THE LEACHING FIELD FOUND TO HAVE UNSUITABLE SOIL MUST BE REPLACED WITH TITLE 5 SAND AS SPECIFIED IN 310 CMR 15.255(3). ANY 11 AREAS THAT ARE FOUND TO HAVE UNSUITABLE MATERIAL SHALL BE REPORTED TO THE ENGINEER.
- 12. ALL SEPTIC COMPONENTS SHALL BE INSTALLED WITH MAGNETIC WARNING TAPE.
- 13. ALL SEPTIC TANKS SHALL BE APPLIED WITH 2 COATS OF DAMP PROOFING OR BITUMINOUS MATERIAL ON THE OUTSIDE OF THE TANKS.
- 14. THE CONTRACTOR SHALL PROVIDE OPERATOR TRAINING FOR EACH OF THE EQUIPMENT PROVIDED INCLUDING ALARM NOTIFICATION.

EFFLUENT DOSING PUMP CONTROL PANEL SPECIFICATION  $\triangle$ USE DUPLEX ALTERNATING PUMPS CAPABLE OF 70 GPM AT 32-FEET OF TDH. THE CONTRACTOR IS RESPONSIBLE FOR SETTING UP THE PUMPS, CONTROL PANEL, FLOAT SWITCH ELEVATIONS, AND ALL ELECTRICAL WIRING WITHIN THE PUMP CHAMBER. THE CONTRACTOR SHALL THEN CONDUCT A STARTUP TEST TO DEMONSTRATE THE PUMP CHAMBER IS FUNCTIONING AS DESIGNED PRIOR TO REQUESTING FOR A CLEAN WATER TEST, WHICH SHALL BE WITNESSED BY THE ENGINEER AND/OR THE LOCAL BOH. THE PUMP ALARM PANEL SHALL BE INSTALLED ON A SEPARATE CIRCUIT FROM THE DOSING PUMPS. THE CONTRACTOR SHALL INCLUDE AN ALLOWANCE FOR COORDINATING, INSTALLING AND PAYING FOR A MISSION MODEL 112 (NEMA 4) RTU REMOTE ALARM UNIT OR APPROVED EQUAL INCLUDING THE FIRST YEAR MONITORING FEE. A 110V OUTLET SHALL BE INSTALLED IN CLOSE PROXIMITY TO THE REMOTE ALARM FINAL LOCATION OF THE UNIT SHALL BE FIELD DETERMINED. MONITORING UNIT. THE FOLLOWING ALARMS SHALL BE MONITORED: DUPLEX PUMP CONTROL PANEL SHALL CONSIST OF THE FOLLOWING: NEMA 4X LOCKABLE ENCLOSURE ALARM LIGHT AND HORN WITH SILENCE SWITCH LOW LEVEL CUT-OFF AND ALARM 8. PANEL SHALL BE SHIPPED LOOSE FOR REMOTE MOUNTING mmmm WASTEWATER INSTALLATION INSPECTION NOTES  $\angle \Delta$ 1. THE CONTRACTOR SHALL PROVIDE A MINIMUM OF 24 HOURS ADVANCE NOTICE TO THE ENGINEER, DEP AND LOCAL BOARD OF HEALTH FOR ANY INSPECTION. 2. ALL WASTEWATER SYSTEMS, INCLUDING THE LEACHING SYSTEM, SHALL BE INSPECTED BY THE ENGINEER AND A THE LOCAL BOH REPRESENTATIVE PRIOR TO BACKFILLING. AT A MINIMUM THE FOLLOWING ITEMS SHALL BE INSPECTED: 2.1. EXCAVATION OF LEACHING FIELD PRIOR TO PLACING SYSTEM STONE/COMPONENTS 2.2. LEACHING FIELD COMPLETE INSTALLATION PRIOR TO BACKFILL 2.3. ALL SYSTEM COMPONENTS BASE AND INSTALLATION PRIOR TO BACKFILL 2.4. START UP TEST OF SYSTEM WITH ALL COMPONENTS INSTALLED AND FUNCTIONING AS DESIGNED 2.5. FINAL INSPECTION OF BACKFILLED SYSTEM


3. THE CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN UP-TO-DATE RED LINED DRAWINGS AND NOTES INDICATING THE HORIZONTAL AND VERTICAL LOCATION WITH TWO TIES OF ALL SYSTEM COMPONENTS INSTALLED. THESE AS-BUILT DRAWINGS AND NOTES WILL BE UTILIZED BY THE ENGINEER FOR THE PREPARATION OF RECORD CLEAR WATER TEST PROTOCOL VERIFY ALL ALARM CONDITIONS ARE FUNCTIONING AS DESIGNED. VERIFY ALL REMOTE ALARMS ARE NOTIFYING THE OPERATOR ACCORDINGLY. VERIFY PUMPS ARE ALTERNATING AS DESIGNED AND DISTAL HEAD REQUIREMENTS ARE MET.

NOTE:


NOTIFY THE ENGINEER 72 HOURS IN ADVANCE OF THE CLEAR WATER TEST. THE SCHEDULE MAY HAVE TO BE ADJUSTED DUE TO AVAILABILITY OF BOH STAFF.





C - 12




TITLE 5 DESIGN FLOW	4,400	GPD
PERFORATIONS		
ERFORATIONS		
PERFORATION DIAMETER, Dp =	1/8	IN.
DISTAL IN-LINE PRESSURE, Hd =	3	FT. (2.5 FT. MIN.)
NUMBER OF PERFORATIONS/LATERAL, N =	15.00	
PERFORATION SPACING, S =	5	FT.
LATERALS		
	_	
LATERAL SPACING, Ls =		FT.
LATERAL DIAMETER, Ld =		IN.
LENGTH OF LATERALS, L =		FT.
HAZEN-WILLIAMS COEFFICIENT, Ch =	140 13	
NUMBER OF LATERALS, Ln =	13	
FORCE MAIN AND MANIFOLD		
FORCE MAIN DIAMETER, Dfm =	1	IN.
LENGTH OF FORCE MAIN, Lfm =	167	
MANIFOLD DIAMETER, Dm =		IN.
MANIFOLD LENGTH, Lm =		FT.
DISCHARGE RATES		
PERFORATION DISCHARGE RATE, q = 11.79 x (Dp)2 x (Hd)1/2 =		GPM
LATERAL DISCHARGE RATE, QI, q × N =		GPM
SYSTEM DISCHARGE RATE, Q, QI x Ln =	63	GPM
DOSING CALCULATIONS		
PIPING SYSTEM VOLUME, Vs =	221	GAL.
DOSE VOLUME, (5.0 x Vs) =	1,659	
DOSE VOLUME 4400 GPD/4 DOSES/DAY =	1,100	
	.,	
USE:	1,431	GALLON DOSE VOLUM
HEAD LOSSES		
FRICTION LOSS IN FORCE MAIN, fl =	0.5	FT.
FRICTION LOSS IN MANIFOLD, fl =	0.3	
	0.2	FT.
NETWORK LOSSES, nl =	3.9	
HEAD LOSS THROUGH DISTRIBUTION VALVE=	17.0	
STATIC HEAD =	10.0	FT.
TOTAL HEAD =	31.9	FT.
PUMP PARAMETERS		
	70	CDM
FLOW, Q = TOTAL DYNAMIC HEAD =	32.0	GPM FT













odified: 12/13/21 printed: 12/13/21 by eh K:\Projects\2019\19038 Cape View Way\Drawings\19038 DE





odified: 12/13/21 printed: 12/13/21 by eh K:\Projects\2019\19038 Cape View Way\Drawings\19038 DE.dw

### ORETENTION CONSTRUCTION SEQUENCE

- HE FOLLOWING CONSTRUCTION SEQUENCE IS TO BE USED AS A GENERAL GUIDELINE. COORDINATE WITH THE OWNER, ENGINEERS, AND LANDSCAPE ARCHITECTS AND SUBMIT A PROPOSED CONSTRUCTION SEQUENCE FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.
- CONDUCT A PRE-CONSTRUCTION MEETING.
- 2. CHECK FOR EXISTING UTILITIES PRIOR TO ANY EXCAVATION.
- 3. CLEAR AND GRUB THE PROPOSED BIORETENTION AREA
- ROUGH GRADE THE BIORETENTION AREA DURING GENERAL CONSTRUCTION. 5. EXCAVATE PRETREATMENT CELLS AND/OR SEDIMENT FOREBAYS PRIOR TO BIORETENTION
- CONSTRUCTION 6. DO NOT CONSTRUCT THE BIORETENTION AREA UNTIL ALL DISTURBED AREAS WITHIN THE CONTRIBUTING
- DRAINAGE AREAS HAVE BEEN GRADED AND STABILIZED. INSTALL TEMPORARY EROSION AND SEDIMENT CONTROLS TO DIVERT STORMWATER AWAY FROM THE **BIORETENTION AREA**
- 3. EXCAVATE THE BIORETENTION FACILITY TO THE BOTTOM INVERT OF THE SUBDRAIN SYSTEM. IF USED FOR TEMPORARY STORMWATER MANAGEMENT DURING CONSTRUCTION PROVIDE A SURFACE ELEVATION AT A MINIMUM 1-FOOT ABOVE THE BOTTOM OF UNDERDRAIN ELEVATION AS SHOWN IN THE BIORETENTION SCHEDULE. THIS ALLOWS FOR AN OVER-DIG OF THE ACCUMULATED SEDIMENT FROM WITHIN THE BIORETENTION AREA PRIOR TO MEDIA/FABRIC INSTALLATION
- PRIOR TO THE INSTALLATION OF FILTER FABRIC AND MEDIA WITHIN THE BIORETENTION AREAS, REMOVE AND PROPERLY DISPOSE OF SEDIMENT ACCUMULATED IN ANY PARTIALLY CONSTRUCTED OR TEMPORARY BIORETENTION/DRAINAGE AREA USED FOR SEDIMENT CONTROL DURING CONSTRUCTION.
- 11. INSTALL THE FILTER FABRIC ALONG THE EXCAVATION SIDE WALLS. <u>ENGINEER FIELD VISIT AND REPORT</u> REQUIRED SEE NOTE (3) BELOW
- 12. RIP THE BOTTOM SOILS TO A DEPTH OF SIX INCHES TO PROMOTE GREATER INFILTRATION.
- 13. INSTALL THE OVERFLOW OUTLET STRUCTURE AS SPECIFIED IN THE DRAWINGS.
- 14. INSTALL UNDERDRAIN AS INDICATED ON DRAWINGS. ENGINEER FIELD VISIT AND REPORT REQUIRED PRIOR TO COVERING THE UNDERDRAIN. SEE NOTE (3) BELOW
- 15. INSTALL PEA GRAVEL LAYER AS INDICATED ON DRAWINGS.
- 16. DELIVER APPROVED BIORETENTION SOIL AND STORE ON ADJACENT IMPERVIOUS AREA OR PLASTIC SHEETING.
- 17. BACKFILL WITH APPROVED BIORETENTION SOIL TO THE DESIGN GRADE (UN-COMPACTED) AS INDICATED ON DRAWINGS. THE CONTRACTOR MUST SUBMIT A SOIL SAMPLE (2 LBS) TO THE ENGINEER PRIOR TO SOIL DELIVERY TO THE SITE
- 18. STABILIZE ALL REMAINING DISTURBED AREAS AND SIDE SLOPES WITH SEEDING, HYDROSEEDING, AND/OR EROSION CONTROL BLANKETS AS INDICATED ON DRAWINGS. ENGINEER FIELD VISIT AND REPORT **REQUIRED SEE NOTE (3) BELOW**
- 19. INSTALL BIORETENTION PLANTINGS AS INDICATED ON DRAWINGS. DO NOT PLANT BEFORE THE REMAINING DISTURBED AREAS SURROUNDING THE FACILITY ARE STABILIZED.
- 20. INSTALL MULCH LAYER AS INDICATED ON DRAWINGS. <u>THE CONTRACTOR MUST SUBMIT A MULCH SAMPLE</u> (1 GALLON) TO THE ENGINEER PRIOR TO DELIVERY TO THE SITE.
- 21. CONDUCT FINAL CONSTRUCTION INSPECTION WITH ENGINEER. ENGINEER FIELD VISIT AND REPORT REQUIRED SEE NOTE (3) BELOW
- 22. REMOVE REMAINING EROSION AND SEDIMENT CONTROLS ONLY AFTER SURROUNDING DISTURBED AREAS HAVE BEEN PROPERLY STABILIZED. NOTES
- (1.) SEE GENERAL CONSTRUCTION NOTES FOR OVERALL CONSTRUCTION SEQUENCE.
- (2.) SEE GENERAL NOTES/SPECIFICATIONS/CONSTRUCTION DETAILS FOR DETAILED CONSTRUCTION REQUIREMENTS (3.) MANDATORY NOTIFICATION/APPROVAL OF THE PROJECT ENGINEER IS REQUIRED PRIOR TO

PROCEEDING WITH NEXT STAGE. CALL THE ENGINEER (HORSLEY WITTEN GROUP, INC.) AT 508-833-6600 PRIOR TO 12:00 NOON THE PROCEEDING DAY TO ARRANGE FOR ANY REQUESTED FIELD VISITS.

### CONSTRUCTION NOTES

- . EXAMINATION
- A. VERIFY LAYOUT AND ORIENTATION OF BIORETENTION AREA AND CONNECTIONS.
- B. VERIFY EXCAVATION BASE IS READY TO RECEIVE WORK AND EXCAVATIONS, DIMENSIONS, AND ELEVATIONS ARE AS INDICATED ON DRAWINGS.
- . PREPARATION
- A. CALL DIGSAFE AT 1-888-DIG-SAFE (1-888-344-7233) NOT LESS THAN THREE BUSINESS DAYS BEFORE PERFORMING WORK.
- B. REQUEST UNDERGROUND UTILITIES TO BE LOCATED AND MARKED WITHIN AND SURROUNDING CONSTRUCTION AREAS.
- C. IDENTIFY REQUIRED LINES, LEVELS, CONTOURS, AND DATUM. D. CLEAR AND GRUB THE PROPOSED BIORETENTION AREA.
- A. EXCAVATE BIORETENTION AREA IN ACCORDANCE WITH GENERAL NOTES AND SPECIFICATIONS.
- B. TO MINIMIZE COMPACTION, WORK EXCAVATORS OR BACKHOES FROM THE SIDES TO EXCAVATE THE BIORETENTION AREA TO ITS APPROPRIATE DESIGN DEPTH AND DIMENSIONS. USE EXCAVATING EQUIPMENT WITH ADEQUATE REACH SO THEY DO NOT WORK IN THE FOOTPRINT OF THE BIORETENTION AREA. IF APPLICABLE AND PER THE ENGINEERS DIRECTION USE A CELL CONSTRUCTION APPROACH IN LARGER BIORETENTION BASINS, WHEREBY THE BASIN IS SPLIT INTO 500 TO 1000 SQUARE FOOT TEMPORARY CELLS WITH A 10 TO 15 FOOT EARTH BRIDGE IN BETWEEN, SO THAT CELLS CAN BE EXCAVATED FROM THE SIDE
- C. EXCAVATE AND SEAL ANY PRETREATMENT CELLS AND/OR SEDIMENT FOREBAYS FIRST AND SEALED TO TRAP SEDIMENTS PER THE DRAWINGS.
- D. ROUGH GRADE THE BIORETENTION AREA DURING GENERAL CONSTRUCTION. EXCAVATE THE BIORETENTION FACILITIES TO WITHIN 1 FOOT OF UNDERDRAIN BOTTOM.
- E. IF THE BIORETENTION AREA IS TO BE USED AS A TEMPORARY DRAINAGE STORAGE BASIN DURING THE EARLY STAGES OF PROJECT CONSTRUCTION, THE SIDE SLOPES SHOULD BE TEMPORARILY STABILIZED AND SILT FENCE INSTALLED ALONG THE TOE OF THE ROUGH GRADED BIORETENTION SLOPES TO MINIMIZE EXCESSIVE SEDIMENTATION OF THE BIORETENTION FLOOR.
- COMPACTION
- A. MINIMIZE COMPACTION OF BOTH THE BASE OF THE BIORETENTION AREA AND THE REQUIRED BACKFILI COMPACTION WILL SIGNIFICANTLY CONTRIBUTE TO DESIGN FAILURE.
- B. USE EXCAVATOR OR BACKHOES TO EXCAVATE THE BIORETENTION AREA
- C. IF THE BIORETENTION AREA IS EXCAVATED USING A LOADER, USE ONLY WIDE TRACK OR MARSH TRACK EQUIPMENT, OR LIGHT EQUIPMENT WITH TURF TYPE TIRES. USE OF EQUIPMENT WITH NARROW TRACKS OR NARROW TIRES, RUBBER TIRES WITH LARGE LUGS, OR HIGH PRESSURE TIRES CAUSE EXCESSIVE COMPACTION RESULTING IN REDUCED INFILTRATION RATES AND STORAGE VOLUMES AND IS NOT ACCEPTABLE.
- D. COMPACTION CAN BE ALLEVIATED AT THE BASE OF THE BIORETENTION FACILITY BY USING A PRIMARY TILLING OPERATION SUCH AS A CHISEL PLOW, RIPPER, OR SUBSOILER. THESE TILLING OPERATIONS ARE PERFORMED TO REFRACTURE THE SOIL PROFILE THROUGH THE 12-IN COMPACTION ZONE. SUBSTITUTE METHODS MUST BE APPROVED BY THE ENGINEER. ROTOILLERS TYPICALLY DO NOT TILL DEEP ENOUGH TO REDUCE THE EFFECTS OF COMPACTION FROM HEAVY EQUIPMENT.
- E. DO NOT COMPACT BIORETENTION SOIL WITH MECHANICAL EQUIPMENT.
- EMBANKMENT/BERM FILL
- A. CONSTRUCT EMBANKMENT/BERM IN ACCORDANCE WITH SPECIFICATIONS AND AS INDICATED ON DRAWINGS
- INSTALLATION
- A. DO NOT CONSTRUCT THE BIORETENTION AREA UNTIL ALL DISTURBED AREAS WITHIN THE CONTRIBUTING DRAINAGE AREAS HAVE BEEN GRADED AND STABILIZED.
- B. REMOVE SEDIMENT ACCUMULATED ALONG THE EXCAVATION FLOOR DURING SITE CONSTRUCTION PRIOR
- TO CONTINUING WITH THE BIORETENTION FACILITY CONSTRUCTION.
- C. FORM BOTTOM OF EXCAVATION TO CORRECT ELEVATION. D. IF INFILTRATION IS PROMOTED, THEN RIP THE BOTTOM SOILS TO A DEPTH OF SIX INCHES TO PROMOTE
- GREATER INFILTRATION. E. INSTALL THE FILTER FABRIC ALONG THE EXCAVATION SIDE WALLS AS SPECIFIED IN THE DRAWINGS. IF FILTER FABRIC IS TO BE INSTALLED PLACE THE FILTER FABRIC ON THE SIDES OF THE BIORETENTION
- AREA WITH A MINIMUM SIX INCH OVERLAP AT ALL JOINTS INSTALL ANY TEMPORARY EROSION AND SEDIMENT CONTROLS TO DIVERT STORMWATER AWAY FROM THE BIORETENTION AREA DURING FINAL CONSTRUCTION AND UNTIL IT IS COMPLETED. SPECIAL PROTECTION MEASURES SUCH AS EROSION CONTROL FABRICS MAY BE NEEDED TO PROTECT
- VULNERABLE SIDE SLOPES FROM EROSION DURING THE CONSTRUCTION PROCESS. G. ESTABLISH ELEVATIONS AND PIPE INVERTS FOR INLETS AND OUTLETS AS INDICATED ON DRAWINGS
- H. INSTALL THE OVERFLOW OUTLET STRUCTURE AS INDICATED ON DRAWINGS. . INSTALL UNDERDRAIN, INCLUDING 4 INCH PERFORATED PIPE, GRAVEL AND FILTER FABRIC ON TOP OF THE UNDERDRAIN GRAVEL AS INDICATED ON DRAWINGS. PLACE GRAVEL AROUND THE UNDERDRAIN PIPE AS INDICATED IN THE DETAILS. OBSERVATION WELLS AND/OR CLEAN-OUT PIPES MUST BE PROVIDED (SEE
- PLANS FOR LOCATION) . INSTALL PEA GRAVEL LAYER AS INDICTED ON DRAWINGS.
- K. DELIVER APPROVED BIORETENTION SOIL AND STORE ON ADJACENT IMPERVIOUS AREA OR PLASTIC SHEETING
- BACKFILLING
- A. BACKFILL WITH APPROVED BIORETENTION SOIL TO THE DESIGN GRADE AS SPECIFIED IN THE DRAWINGS. B. PLACE SOIL IN 12 INCH LIFTS UNTIL DESIRED TOP ELEVATION OF BIORETENTION SOIL IS ACHIEVED. DO NOT USE HEAVY EQUIPMENT WITHIN THE BIORETENTION BASIN. HEAVY EQUIPMENT CAN BE USED AROUND THE PERIMETER OF THE BASIN TO SUPPLY SOILS AND SAND. WAIT 3 DAYS TO CHECK FOR

SETTLEMENT, AND ADD ADDITIONAL MEDIA AS NEEDED

- C. DO NOT COMPACT BIORETENTION SOIL WITH MECHANICAL EQUIPMENT
- D. GRADE BIORETENTION MATERIALS WITH LIGHT EQUIPMENT SUCH AS A COMPACT LOADER OR A DOZER/LOADER WITH MARSH TRACKS.
- E. STABILIZE ALL REMAINING DISTURBED AREAS AND SIDE SLOPES WITH SEEDING, HYDROSEEDING, AND/OR EROSION CONTROL BLANKETS AS INDICATED ON DRAWINGS.
- 8. PLANTING
- A. PLANT BIORETENTION AREA IN ACCORDANCE WITH PLANTING PLANS AND SPECIFICATIONS. B. THE PRIMARY FUNCTION OF THE BIORETENTION STRUCTURE IS TO IMPROVE WATER QUALITY. DO NOT ADD FERTILIZERS OR OTHER SOIL AMENDMENTS TO THE BIORETENTION SOILS UNLESS INSTRUCTED BY THE ENGINEER. THE PLANTING SOIL SPECIFICATIONS PROVIDE ENOUGH ORGANIC MATERIAL TO ADEQUATELY SUPPLY NUTRIENTS FROM NATURAL CYCLING.
- C. INSTALL BIORETENTION PLANTINGS AS INDICATED ON DRAWINGS. WATER DURING WEEKS OF NO RAIN FOR THE FIRST TWO MONTHS.
- D. DO NOT PLANT BEFORE THE REMAINING DISTURBED AREAS SURROUNDING THE FACILITY ARE STABILIZED.
- E. REMOVE SEDIMENT ACCUMULATED IN THE BIORETENTION AREA DURING THE PLANTING PHASE F. IF SUITABLE VEGETATIVE COVER HAS NOT BEEN ESTABLISHED ALONG THE BIORETENTION SIDE SLOPES PRIOR TO PLANTING. INSTALL A SILT FENCE PERIMETER AT THE TOE OF THE BIORETENTION SLOPES AND LEAVE IN PLACE UNTIL AN APPROVED VEGETATIVE COVER HAS BEEN ESTABLISHED
- G. INSTALL MULCH LAYER AS INDICATED ON DRAWINGS. MIX APPROXIMATELY HALF OF THE SPECIFIED MULCH LAYER INTO THE BIORETENTION SOIL TO A DEPTH OF APPROXIMATELY 4 INCHES TO HELP FOSTER A HIGHLY ORGANIC SURFACE LAYER.
- H. REMOVE REMAINING EROSION AND SEDIMENT CONTROLS ONLY AFTER SURROUNDING DISTURBED AREAS HAVE BEEN PROPERLY STABILIZED.
- I. CONDUCT FINAL CONSTRUCTION INSPECTION WITH ENGINEER
- 9. CLEAN UP
- A. AFTER COMPLETION OF THE WORK, REMOVE AND PROPERLY DISPOSE ALL DEBRIS, CONSTRUCTION MATERIALS, RUBBISH, EXCESS SOIL, ETC., FROM THE PROJECT SITE. REPAIR PROMPTLY ANY IDENTIFIED DEFICIENCIES AND LEAVE THE PROJECT SITE IN A CLEAN AND SATISFACTORY CONDITION.

### MATERIAL SPECIFICATIONS

BIORETENTION SC SUBMIT SOIL SAMPLE (2LBS) AND TESTING ANALYSIS RESULTS BY A QUALIFIED SOIL TESTING LABORATORY

- INDICATING AND INTERPRETING TEST RESULTS FOR COMPLIANCE WITH THE FOLLOWING PARAMETER: A. UNIFORM SOIL MIX, FREE OF NOXIOUS WEEDS AND STONES, STUMPS, ROOTS OR OTHER SIMILAR
- OBJECTS LARGER THAN 1 INCH. B. PROVIDE USDA UNIFIED SOIL CLASSIFICATION: LOAMY SAND
- C. PROVIDE A TEXTURAL ANALYSIS INCLUDING THE GRADATION AND PERCENTAGES OF SAND, SILT, AND CLAY CONTENT
- 85-88% SAND (< 10% COARSE SAND)
- 8-12% SILT AND CLAY (< 2% CLAY) D. ORGANIC MATTER: 3%
- WELL AGED (6-12 MONTHS), WELL AERATED, LEAF COMPOST OR APPROVED EQUIVALENT E. PROVIDE A SOIL TEST OF THE BIORETENTION SOIL FOR CONFORMANCE TO THE FOLLOWING CRITERIA:
  - PH RANGE: 5.2-7.0. MAGNESIUN MINIMUM 32 PPM PHOSPHOROUS (P2O5):
    - NOT TO EXCEED 69 PPM MINIMUM 78 PPM NOT TO EXCEED 500 PPM
- SOLUBLE SALTS: IF THE SOIL PH IS NOT WITHIN THE ACCEPTABLE RANGE, AMEND WITH LIME TO RAISE THE PH OR WITH IRON SULFATE TO LOWER THE PH, AS NECESSARY. ALL TESTING SHOULD BE PERFORMED BY THE SAME
- TESTING FACILITY TO MAINTAIN CONSISTENT RESULTS. SUBMIT THE SOIL SAMPLE RESULTS TO THE ENGINEER REVIEW AND APPROVAL PRIOR TO DELIVERY TO THE PROJECT SITE.
- F. VOLUME OF FILTER MEDIA BASED ON 110% OF PLAN VOLUME TO ACCOUNT FOR SETTLING OR COMPACTION.
- G. DO NOT MIX, DUMP OR STORE ANY OTHER MATERIALS OR SUBSTANCES THAT MAY B E HARMFUL TO PLANT GROWTH OR PROVE A HINDRANCE TO THE PLANTING MAINTENANCE OR OPERATIONS WITHIN THE BIORETENTION AREA
- 2. FILTER FABRIC
- B. NON-WOVEN GEOTEXTILE FABRIC WITH FLOW RATE OF > 110 GALLON/MINUTES/SQUARE FOOT. C. CLASS "C" APPARENT OPENING SIZE (ASTM-D-4751).
- D. GRAB TENSILE STRENGTH (ATSM-D-4632) BURST STRENGTH (ASTM-D-4833).
- 3. PEA GRAVEL

POTASSIUM (K2O):

- A. 3/8" WASHED STONE
- 5. UNDERDRAIN GRAVEL
- A. 3/4" CRUSHED WASHED STONE, CLEAN AND FREE OF ALL FINES AND MEETING AASHTO M-43. 6. <u>PIPE</u>
- A. UNDERDRAIN

8. PLANTS

- 4" RIGID SCHEDULE 40 PVC PIPE, WITH 3/8" PERFORATIONS @ 6" O.C. MEETING ASTMD 1785 OR AASHTO T'S AND Y'S FITTINGS AS REQUIRED FOR THE UNDERDRAIN CONFIGURATION INDICATED ON DRAWING
- B. CONNECTIONS TO STORM DRAIN SYSTEM.
- C. UNDERDRAIN CLEANOUTS

A. AS INDICATED ON DRAWINGS.

A. SIZE AS INDICATED ON DRAWINGS.

9. SEED (SIDE SLOPES ONLY)

10. OUTLET STRUCTURE

TOF INTO

SLOPE

2' MIN.

2. GROUT ABUTTING SECTIONS OF GRANITE CURBING.

18" MIN

NON PERFORATED SCHEDULE 40 PVC PIPE, PVC ELBOW, CAP, AND ALL ASSOCIATED FITTINGS. 7. EROSION CONTROL BLANKET (3:1 SIDE SLOPES ONLY)

A. NEW ENGLAND CONSERVATION/WILDLIFE/MIX OR APPROVED EQUIVALENT.

SEE PLANS


BOTTOM FOREBAY


PROFILE

GROUT ABUTTING SECTIONS


A. WOVEN, 100% BIODEGRADABLE JUTE FIBER 7.70 LBS/1000 SQFT.

BIONET S150BN OR APPROVED EQUIVALENT.






1. KEY GRANITE CURBING INTO THE FOREBAY SIDE SLOPES AND EXTEND A MINIMUM OF 2' TO PREVENT FLOW FROM DIVERTING THE CHECK DAM





	・ Revised per peer review comments 会 12/10/21 EWH BRK Revised per peer review comments 会 12/10/21 EWH BRK Revised schedule	Checked By: BRK
	Horsley Witten Group, Inc. Sustainable Environmental Solutions www.horsleywitten.com 90 Route 6A Sandwich, MA 02563 508-833-6600 voice 508-833-3150 fax	Date: Designed By: Drawn By: MARCH 5, 2021 EWH EWH
	CAPE VIEW WAY PERMITTING PLANS BOURNE, MASSACHUSETTS	CONSTRUCTION DETAILS (5)
	Prepared For: PRESERVATION OF AFFORDABLE HOUSING 2 OLIVER STREET, SUITE 500 BOSTON, MA 02109 Phono. (617) 261-0808	Fax: Plan Title:
	Survey Provided By: Horsley Witten Group, Inc. 90 Route 6A Sandwich, MA 02563 Phone: (508) 833-6600 Fax: (508) 833-3150 Dated: JUNE 2019	
	Registration: RICHARD A. CLAYTOR CIVIL NO. 45116 RCISHEN 12-13-202	
PERMITTING SET ONLY NOT FOR CONSTRUCTION	-	of 22 B





Suggested Plant List	t	
	$ \land \land \land \land \land$	$\overline{}$
Trees		Size
Street/Large Deciduous		
Acer rubrum	Red Maple	3-3.5" cal.
Nyssa sylvatica	Tupelo	3-3.5" cal.
Quercus alba	White Oak	3-3.5" cal.
Quercus coccinea	Scarlet Oak	3-3.5" cal.
Quercus rubra	Red Oak	3-3.5" cal.
Ulmus americana	American Elm	3-3.5" cal.
Ornamental	· · · · · · · · · · · · · · · · · · ·	
Amelanchier sp.	Serviceberry	6/7' B&B
Betula papyrifera	Paper Birch	10-12' clump
Betula populifolia	Gray Birch	10-12' clump
Evergreen		
	Eastem Red Cedar	8-10' min.
Juniperus virginiana Pinus strobus	White Pine	8-10' min.
Pinus strobus	vvnite Pine	o-10 min.
Foundation Plants		
Shrubs		
Aronia sp.	Chokeberry	24" min. ht.
Clethra alnifolia	Summersweet Clethra	24" min. ht.
Comptonia peregrina	Sweetfern	24" min. ht.
Cornus sericea	Red Twig Dogwood	24" min. ht.
llex glabra	Inkberry	24" min. ht.
Hydrangea quercifolia	Oakleaf Hydrangea	24" min. ht.
Hypericum kalmianum	Kalm St. Johnswort	24" min. ht.
Morella pensylvanica	Bayberry	24" min. ht.
Physocarpus opulifolius	Ninebark	24" min. ht.
Rhus aromatica 'Gro Low'	Fragrant Sumac	24" min. ht.
Vaccinium sp.	Blueberry	24" min. ht.
Vibumum dentatum	Arrowwood	24" min. ht.
Perennials/Grasses/Groun	dcovers	
Geum fragarioides	Appalachian Barren Strawberry	#1
Geranium maculatum	Wild Geranium	#1
Heuchera macrorhiza	Coral Bells	#1
Oenothera fruticosa	Evening Primrose	#1
Osmunda cinnamomea	Cinnamon Fern	#1
Pycanthemum sp.	Mountain Mint	#1
Schizachyrium scoparium	Little Bluestem	#1
Sporobolus heterolepsis	Prairie Dropseed	#1

Buffer Plants		Size
Trees		
Acer rubrum	Red Maple	3-3.5" cal.
Amelanchier sp.	Serviceberry	6/7' B&B
Nyssa sylvatica	Tupelo	3-3.5" cal.
Prunus serotina	Black Cherry	3-3.5" cal.
Quercus alba	White Oak	3-3.5" cal.
Quercus bicolor	Swamp White Oak	3-3.5" cal.
Shrubs		
Clethra alnifolia	Summersweet Clethra	24" min. ht.
Viburnum dentatum	Arrowwood Viburnum	24" min. ht.
Perennials/Grasses/Groun		
Carex sp.	Sedge sp.	#1
Osmunda cinnamomea	Cinnamon Fem	#1
Parking Lot Islands		
Shrubs		
Comptonia peregrina	Sweetfern	24" min. ht.
Hypericum sp.	St. Johnswort	24" min. ht.
Rhus aromatica 'Gro Low'	Fragrant Sumac	24" min. ht.
		24 1111. 11.
Perennials/Grasses/Groun	ndcovers	
Coreopsis sp.	Coreopsis	#1
Baptisia tinctoria	Yellow Wild Indigo	#1
Eupatorium hyssopifolium	Hyssop Leaved Boneset	#1
Geum fragarioides	Appalachian Barren Strawberry	#1
Oenothera fruticosa	Sundrops	#1
Sporobolus heterolepsis	Prairie Dropseed	#1
Stormwater Managemen	t Areas	
Trees	D'al	10.101
Betula sp.	Birch	10-12' clump
Nyssa sylvatica	Tupelo	3-3.5" cal.
Shrubs		
Clethra alnifolia	Summersweet Clethra	24" min. ht.
Cornus sericea	Red Twig Dogwood	24" min. ht.
Perennials/Grasses/Groun	dcovers	
Asclepias sp.	Milkweed sp.	#1
Carex sp.	Sedge sp.	#1
Eragrostis spectabilis	Purple Lovegrass	#1
Eupatorium hyssopifolium	Hyssop Leaved Boneset	#1
Juncus sp.	Rushes	#1
Panicum virgatum	Switchgrass	#1
Penstemon digitalis	Beardtongue	#1
Pycanthemum sp.	Mountain Mint	#1
Schizachyrium scoparium	Little Bluestem	#1
Solidago sp.	Goldenrod	#1









nodified: 12/13/21 printed: 12/13/21 by eh K:\Projects\2019\19038 Cape View Way\Drawings\19038 L

### GENERAL PLANTING NOTES:

- THE FOLLOWING NOTES ARE PROVIDED AS GENERAL PLANTING GUIDELINES ONLY. THOROUGHLY REVIEW THE PROJECT SPECIFICATIONS FOR ALL LANDSCAPE REQUIREMENTS PRIOR TO THE COMMENCEMENT OF ANY LANDSCAPE WORK. SUBMIT IN WRITING TO THE LANDSCAPE ARCHITECT ANY QUESTIONS OR CLARIFICATIONS REQUIRED AT A MINIMUM OF 30 DAYS PRIOR TO ORDERING ANY MATERIALS OR BEGINNING ANY LANDSCAPE CONSTRUCTION.
- SUBMIT TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL ALL REQUIRED LANDSCAPE SUBMITTALS AS DESCRIBED IN THE SPECIFICATIONS INCLUDING A PLANT LIST WITH PLANT SIZE AND QUANTITIES TO BE ORDERED PRIOR TO DELIVERY TO THE PROJECT SITE.
- FURNISH AND INSTALL ALL PLANTS AS SHOWN ON THE DRAWINGS AND IN THE SIZE AND QUANTITIES SPECIFIED ON THE PLANTING SCHEDULE. PLANT SUBSTITUTION SELECTION MUST BE APPROVED BY BIOLOGIST OR LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- ALL PLANTS TO COMPLY WITH APPLICABLE REQUIREMENTS OF ANSI Z60.1 "AMERICAN STANDARD FOR NURSERY STOCK." LATEST EDITION, PUBLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION INC.
- PLANTS TO BE GROWN UNDER CLIMATIC CONDITIONS SIMILAR TO THOSE IN THE LOCALITY OF THE PROJECT FOR AT LEAST TWO (2) YEARS. USE HEALTHY NURSERY GROWN PLANTS THAT HAVE A WELL DEVELOPED ROOT SYSTEM. PLANTS MUST BE FREE OF DISEASE, INSECTS, EGGS OR LARVAE
- INSTALL PLANTS WITHIN ONE (1) WEEK OF PURCHASE. IF PLANTS ARE TO BE STORED AT THE SITE PRIOR TO PLANTING, IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THEY ARE PROPERLY MAINTAINED, WATERED, AND REMAIN HEALTHY.
- PROCEED WITH PLANTING ONLY WHEN EXISTING AND FORECASTED WEATHER CONDITIONS PERMIT. SUBMIT TO THE LANDSCAPE ARCHITECT IN WRITING THE PROPOSED PLANTING SCHEDULE. OBTAIN APPROVAL OF PLANTING SCHEDULE FROM THE LANDSCAPE ARCHITECT PRIOR TO PERFORMING ANY WORK.
- SEASONS FOR PLANTING:

SPRING:	DECIDUOUS:	APRIL 1 TO JUNE 15
	EVERGREEN:	APRIL 1 TO JUNE 15
	PERENNIALS:	APRIL 15 TO JUNE 1
	GROUNDCOVERS:	APRIL 15 TO JUNE 1
FALL:	DECIDUOUS:	SEPTEMBER 15 TO NOVEMBER
	EVERGREEN:	SEPTEMBER 15 TO NOVEMBER
	PERENNIALS:	SEPTEMBER 15 TO NOVEMBER

GROUNDCOVERS: SEPTEMBER 15 TO NOVEMBER 15

- PLANTING UNDER FROZEN CONDITIONS IN EITHER THE SPRING OR FALL WILL NOT BE PERMITTED. PLANTING BEFORE OR AFTER THE ABOVE REFERENCED PLANTING DATES WILL INCREASE THE LIKELIHOOD OF PLANT OR GRASS SEED ESTABLISHMENT FAILURE. ANY DEVIATION FROM THE ABOVE REFERENCED PLANTING DATES IS UNDERTAKEN AT SOLE RISK OF THE CONTRACTOR AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE ANY ADDITIONAL MAINTENANCE AND WATERING WHICH MAY BE REQUIRED TO ENSURE SATISFACTORY PLANT AND SEED ESTABLISHMENT.
- 10. FURNISH ONE YEAR MANUFACTURER WARRANTY FOR TREES, PLANTS, AND GROUND COVER AGAINST DEFECTS INCLUDING DEATH AND UNSATISFACTORY GROWTH. EXCEPTIONS ARE DEFECTS RESULTING FROM LACK OF ADEQUATE MAINTENANCE, NEGLECT OR ABUSE BY OWNER, OR ABNORMAL WEATHER CONDITIONS UNUSUAL FOR WARRANTY PERIOD. THE DATE OF FINAL ACCEPTANCE OF ALL COMPLETED PLANTING WORK ESTABLISHES THE END OF INSTALLATION AND INITIAL MAINTENANCE PERIOD AND THE COMMENCEMENT OF THE GUARANTEE PERIOD.
- 11. ALL TREES WITHIN 5'-0" OF WALKWAYS AND SIDEWALKS TO HAVE A 6'-8" STANDARD BRANCHING HEIGHT.
- 12. INSPECT ALL AREAS TO BE PLANTED OR SEEDED PRIOR TO STARTING ANY LANDSCAPE WORK. REPORT ANY DEFECTS SUCH AS INCORRECT GRADING INCORRECT SUBGRADE ELEVATIONS OR DRAINAGE PROBLEMS, ETC. TO THE LANDSCAPE ARCHITECT AND ENGINEER PRIOR TO BEGINNING WORK COMMENCEMENT OF WORK INDICATES ACCEPTANCE OF SUBGRADE AREAS TO BE PLANTED, AND THE LANDSCAPE CONTRACTOR ASSUMES RESPONSIBILITY FOR ALL LANDSCAPE WORK.
- 3. PROVIDE PROPER PREPARATION OF ALL PROPOSED PLANTED AND SEEDED AREAS PER THE NOTES AND SPECIFICATIONS.
- 4. ALL PLANT LAYOUT AND ACTUAL PLANTING LOCATIONS ARE TO BE FIELD VERIFIED BY LANDSCAPE ARCHITECT PRIOR TO PLANTING. NOTIFY THE LANDSCAPE ARCHITECT AT A MINIMUM OF 48 HOURS IN ADVANCE PRIOR TO SCHEDULING ANY FIELD INSPECTIONS.
- 5. BALL AND BURLAP: REMOVE BURLAP AND WIRE BASKETS FROM TOPS OF BALLS AND FROM TOP HALF OF ROOTBALL AS INDICATED ON DRAWINGS. REMOVE PALLETS, IF ANY, BEFORE SETTING.
- 16. POTTED PLANTS: REMOVE THE PLANT FROM THE POT AND LOOSEN OR SCORE THE ROOTS BEFORE PLANTING TO PROMOTE OUTWARDS ROOT GROWTH INTO THE SOIL.
- 17. PLUGS: PLANT UPRIGHT AND NOT AT AN ANGLE. DIG PLANTING HOLES LARGE ENOUGH AND DEEP ENOUGH TO ACCOMMODATE THE ENTIRE ROOT MASS. PLANT PLUGS WITH NO TWISTED OR BALLED ROOTS AND WITH NO ROOTS EXPOSED ABOVE THE GRADE LINE. HAND PACK THE SOIL AROUND THE ENTIRE PLUG ROOT MASS
- 18. DIG THE THE PLANTING HOLE TO THE SAME DEPTH AS THE ROOT BALL AND TWO TO THREE TIMES WIDER. SCORE ALL SIDES OF THE HOLE, PLACE THE PLANT IN THE HOLE SO THE TOP OF ROOT BALL IS EVEN WITH SOIL SURFACE. FILL THE HOLE HALFWAY AND THEN ADD WATER ALLOWING IT TO SEEP INTO BACK FILLED MATERIAL. BE SURE TO REMOVE ALL AIR POCKETS FROM BACK FILLED SOIL. DO NOT SPREAD SOIL ON TOP OF THE ROOTBALL. IF SOIL IS EXTREMELY POOR, REPLACE BACK FILL WITH GOOD QUALITY TOP SOIL. AMEND THE SOIL, AS NECESSARY.
- 19. CREATE A 2" TO 4" BERM AROUND THE EDGE OF PLANTING HOLE WITH REMAINING SOIL TO RETAIN WATER.
- 20. REMOVE ALL PLANT TAGS AND FLAGS FROM THE PLANTS.
- 21. MULCH ALL PLANTING BEDS AS INDICATED ON DRAWINGS. UNLESS NOTED OTHERWISE, ALL PLANTS TO RECEIVE 2-3 INCHES OF MULCH. DO NOT PILE OR MOUND MULCH AROUND THE PLANT STEMS OR TRUNK.
- 22. TRIM BROKEN AND DEAD BRANCHES FROM TREES AND SHRUBS AFTER PLANTING. NEVER CUT A LEADER.

### GENERAL SEEDING NOTES:


- THE TESTING AGENCY.
- SPECIFIED ON THE PLANS.
- MATTER AND LEGALLY DISPOSE TO AN OFF SITE LOCATION.
- COMPACTED OR NOT PROPERLY PREPARED PER THE NOTES AND SPECIFICATIONS.


5. SEE SPECIFICATIONS FOR SEASONAL REQUIREMENTS FOR SEEDING.

- THE APPROVED SCHEDULE UNTIL PLANTS ARE FULLY ESTABLISHED.
- THE RECOMMENDED PLANTING SEASONS.

### PLANTING LAYOUT NOTES

DEPENDING ON THE OVERALL NUMBER OF PLANTINGS.





NOT TO SCALE